MILITARY SPECIFICATION

PROJECTOR, PYROTECHNIC
PARTS FOR AND ASSEMBLING AND PACKING

1. SCOPE

1.1 This specification covers the parts for and the assembling and packing for one type of pyrotechnic projector.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein.

SPECIFICATIONS

MILITARY

MIL-P-116 - Preservation, Methods of
MIL-A-2550 - Ammunition and Special Weapons; General Specification for

STANDARDS

MILITARY

MIL-STD-105 - Sampling Procedures and Tables for Inspection by Attributes (ABC-STD-105)
MIL-STD-109 - Quality Assurance Terms and Definitions
MIL-STD-171 - Finishing of Metal and Wood Surfaces
MIL-STD-810 - Environmental Test Methods
MIL-STD-1167 - Ammunition Data Cards
MIL-STD-1168 - Lot Numbering of Ammunition
MIL-STD-1234 - Pyrotechnics; Sampling, Inspection and Testing
MIL-STD-1235 - Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes

FSC: 1370

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

DRAWINGS

U. S. ARMY MUNITIONS COMMAND

9229014 - Projector, Pyrotechnic
9234284 - Carton, Packing For, Projector, Pyrotechnic
9234285 - Box, Packing For, Projector, Pyrotechnic
8796522 - Marking Diagram and Sealing for Wood Packing Boxes

PUBLICATIONS

U. S. ARMY MUNITIONS COMMAND

ET - 9229014 - quipment Tabulation

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material.-Materials and parts shall be in accordance with applicable drawings and specifications.

3.2 Assembly.-The assembly shall comply with all requirements specified on Drawing (dwg.) 9229014 and with all requirements in applicalbe specifications.

3.3 Functioning.-The projector assembly shall not fail to initiate any Alcan 220 primer assembled in a test plug when tested as specified in 4.4.1.

3.4 Salt fog.-The projector assembly shall comply with the requirements of 3.3 after being subjected to the test as specified in 4.4.2.

3.5 Aircraft vibration.-The projector shall comply with the requirements of 3.3 after being subjected to the test as specified in 4.4.3.

3.6 Embrittlement of spring.-The spring (see dwg. 9229006) shall not break when stretched to the point of minimum permanent distortion, when tested as specified in 4.4.4.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

3.7 Workmanship.-All parts and assemblies shall be fabricated and finished in a thorough workmanlike manner. They shall be free of burrs, chips, sharp edges, cracks, surface defects, dirt, grease, rust, corrosion products and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Exterior surface coatings shall be continuous except for a few light scratches not exposing base material. All required markings shall be neat and sharply defined.

3.8 First article inspection.-This specification makes provisions for first article inspection. Requirements for the submission of first article samples by the contractor shall be as specified in the contract.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for inspection.-Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified in the contract or order, the supplier may use his own or any other facilities suitable for the performance of the inspection requirements specified herein, unless disapproved by the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services comform to prescribed requirements. Reference shall be made to MIL-STD-109 to define terms used herein. The provisions of MIL-A-2550 shall apply.

4.1.1 Submission of product.-At the time each completed lot of items deliverable under the contract is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

a. A statement that the lot complies with all of the quality assurance provisions specified in this specification.
b. Drawing and specification number and date, together with identification and date of changes thereto.
c. A statement that all material purchased by the contractor meets requirements when such material is controlled by Government or commercial specifications referenced in any of the contractual documents, and that certificates of conformance are on file and available for review.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

d. Number of items in the lot.
e. Date submitted.
f. A statement that the components and assemblies were assembled as required by the drawings.

The certificate shall be signed by a responsible agent of the ceritfying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.2 First article inspection

4.2.1 Submission.-The contractor shall submit a first article sample as designated by the contracting officer for evaluation in accordance with the provisions of 4.2.2. The first article sample shall consist of twenty-five (25) complete sets of parts (i.e., 25 each of every component and sub-assembly) which have been produced by the contractor or furnished by a supplier and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing components shall be obtained from the same source of supply as will be used in regular production. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conformes to the requirements of the contract and he shall submit a record of this inspection with the sample, including certificates of conformance of materials. A sample containing known defects shall not be submitted unless specifically authorized by the contracting officer. A first article sample, or portion therof, as directed by the contracting officer shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, materials used, drawing or specification such as to significantly affect product uniformity as determined by the Government. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit an additional sample or portion thereof of items for first article inspection. Until a first article sample is accepted, the contractor is in no way authorized by the Government to initiate regular production, unless otherwise directed by the Contracting Officer.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

4.2.2 First article inspection provisions

4.2.2.1 Parts.-The parts submitted will be subjected by the Government to any or all of the applicable examinations and tests specified in 4.3.2 and 4.3.3 of this specification and any or all requirements of the applicable drawings.

4.2.2.1.1 Rejection.-If any component or sub-assembly fails to comply with any of the applicable requirements, the first article sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of a component or sub-assembly to comply with any of the stated requirements.

4.3 Inspection provisions

4.3.1 Lot formation.-The term "inspection lot" as used in this specification is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance with applicable requirements. The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the inspection lot has been produced by one manufacturer in one unchanged process, using the same materials and methods in accordance with the same drawings, same drawing revisions, same specifications and same specification revisions and complies with the provisions for submission of product as specified in MIL-STD-105. Changes to the process, specifications, or drawings not affecting safety, performance, interchangeability, or storage, as determined by the Government, shall not be deemed to alter the homogeneity of an inspection lot. All material submitted for inspection in accordance with this specification shall comply with the homogeneity criteria specified herein regardless of the type of sampling procedure which is being applied to determine conformance with requirements. Lot numbering, as required, shall be in accordance with MIL-STD-1168. Each inspection lot of projector assemblies shall contain parts of one interfix number from one supplier.

4.3.2 Examination.-The examinations listed in the following sub-paragraphs shall be performed on inspection lots (see 4.3.1) of the components or assemblies designated in the applicable

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

paragraph headings. Inspection for critical defects (and major defects, when so specified) shall be 100 percent. Sampling plans for major and minor defects shall be in accordance with MIL-STD-105 except that continuous sampling plans in accordance with MIL-STD-1235 may be used if approved by the Government. Instead of applying the AQL's designated herein to the groups of major and minor defects listed, the contractor may elect to apply AQL's to individual defects using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. When this method is elected, it shall be applied to all of the major and minor defects listed in the applicable sub-paragraph of this section, except where 100 percent inspection is specified, and be documented as part of the contractor's inspection system. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Plug, cap (see dwg. 9229007 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No. (see 6.2)
Critical:	None defined		
Major:	None defined		
Minor:	AQL 4.00 percent		
201.	Length	Gage	01001
202.	Length to shoulder	Gage	01002
203.	Outside diameter before knurl	Gage	01003
204.	Inside diameter	Gage	01004
205.	Outside diameter at threaded end	Gage	01005
206.	Any chamfer missing	Visual	01006
207.	Pitch diameter of thread minimum (min.)	Gage	01007
208.	Major diameter of thread (min.)	Gage	01008
209.	Evidence of poor workmanship (see 3.7)	Visual	01009

4.3.2.2 Eyebolt (see dwg. 9229011 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

Critical: None defined

Major: None defined

Minor:		AQL 1.50 percent	
201.	Length	Gage	02001
202.	Diameter of eye	Gage	02002
203.	Evidence of poor workmanship (see 3.7)	Visual	02003

4.3.2.3 Cap plug assembly (see dwg. 9229013 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Washer missing	Visual	03001
102.	Eyebolt not properly assembled	Visual-Manual	03002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	03003

4.3.2.4 Nut, retainer (see dwg. 9229005 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No,
Critical:	None Defined		
Major:	AQL 0.65 percent		
101.	True position of center hole with pitch diameter of thread	Gage	04001
102.	Diameter of center hole	Gage	04002
103.	Pitch diameter of thread (min.)	Gage	04003
104.	Major diameter of thread (min.)	Gage	04004
Minor:	AQL 2.50 percent		
201.	Width of slot	Gage	04005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

202.	Depth of slot	Gage	04006
203.	Length	Gage	04007
204.	Any chamfer missing	Visual	04008
205.	Evidence of poor workmanship (see 3.7)	Visual	04009

4.3.2.5 Body, projector (see dwg. 9229008 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Total length	Gage	05001
102.	Length to trigger screw slot	Gage	05002
103.	Length of trigger screw slot	Gage	05003
104.	Width of trigger screw slot	Gage	05004
105.	Depth of thread at unknurled end	Gage	05005
Minor:	AQL 2.50 percent		
201.	Depth of thread at knurled end	Gage	05006
202.	Pitch diameter of thread (both ends)(max.)	Gage	05007
203.	Minor diameter of thread (both ends) maximum (max.)	Gage	05008
204.	Length of knurl	Gage	05009
205.	Inside diameter	Gage	05010
206.	Any radius missing	Visual	05011
207.	Evidence of poor workmanship (see 3.7)	Visual	05012

4.3.2.6 Body assembly (see dwg. 9230141 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Depth to retainer nut	Gage	06001
102.	Retainer nut improperly or inadequately staked	Visual-Manual	06002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7)	Visual	06003

4.3.2.7 Screw, trigger (see dwg. 9229010 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Length to shoulder	Gage	07001
102.	Length of thread	Gage	07002
Minor:	AQL 2.50 percent		
201.	Total length	Gage	07003
202.	Small outside diameter, (min.)	Gage	07004
203.	Outside diameter	Gage	07005
204.	Pitch diameter of thread, (min.)	Gage	07006
205.	Major diameter of thread, (min.)	Gage	07007
206.	Knurl missing	Visual	07008
207.	Evidence of poor workmanship (see 3.7)	Visual	07009

4.3.2.8 Pin, firing (see dwg. 9229009 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Total length	Gage	08001
102.	Length to shoulder	Gage	08002
103.	Length to screw hole	Gage	08003
104.	Outside diameter	Gage	08004
105.	Small outside diameter	Gage	08005
106.	True position of small outside diameter with outside diameter	Gage	08006
107.	Firing pin (point) not spherical	Visual	08007
Minor:	AQL 1.50 percent		
201.	Pitch diameter of thread, max	Gage	08008

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

202.	Minor diameter of thread, max.....	Gage	08009
203.	Evidence of poor workmanship (see 3.7).....	Visual	08010

4.3.2.9 Spring (see dwg. 9229006 covering a detail of dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Outside diameter.....	Gage	09001
102.	Free length.....	Gage	09002
103.	Load at compressed length.....	Gage	09003
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.7).....	Visual	09004

4.3.2.10 Projector, pyrotechnic (see dwg. 9229014).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Any component or sub-assembly missing, loose or improperly assembled.....	Visual-Manual	10001
102.	Assembly damaged.....	Visual	10002
103.	Assembly fails to operate freely throughout the range of required motion.....	Manual	10003
Minor:	AQL 1.00 percent		
201.	Marking misleading or unidentifiable.....	Visual	10004
202.	Evidence of poor workmanship (see 3.7).....	Visual	10005

4.3.2.11 Carton, prior to sealing (see dwg. 9234284).

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Carton cut, punctured or torn in any area	Visual	11001
Minor:	AQL 1.50 percent		
201.	Any packing material missing	Visual	11002
202.	Incorrect number of projectors	Visual	11003
203.	Trigger screw in cocked position	Visual	11004

4.3.2.12 Sealed carton (see dwg. 9234284).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Bag punctured, torn or seal incomplete	Visual	12001
Minor:	AQL 1.50 percent		
201.	Contents loose	Manual	12002
202.	Marking misleading or unidentifiable	Visual	12003
203.	Label missing	Visual	12004

4.3.2.13 Packing box, prior to closing (see dwg. 9234285).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	None defined		
Minor:	AQL 1.00 percent		
201.	Any packing material missing	Visual	13001
202.	Incorrect number of cartons	Visual	13002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

4.3.2.14 Sealed packing box (see dwgs. 9234285 and 8796522).

Categories	Defects	Method of Inspection	Code No.
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Board broken or split so that contents are exposed or liable to become exposed	Visual	14001
102.	Hardware or strapping broken or loose	Visual-Manual	14002
103.	DOD symbol missing or incorrect	Visual	14003
Minor:	AQL 1.50 percent		
201.	Hardware or strapping improperly engaged	Visual	14004
202.	Car seal missing, unsealed or mislocated	Visual-Manual	14005
203.	Contents loose	Manual	14006
204.	Marking misleading or unidentifiable	Visual	14007

4.3.3 Testing

4.3.3.1 Functioning (see 3.3) - Major defect - Code No. 10006.-Ten (10) projectors shall be selected from each lot for test. The lot shall be rejected if any projector fails to initiate seven (7) primers each. The test shall be as specified in 4.4.1. (destructive).

4.3.3.2 Salt fog (see 3.4) - Major defect - Code No. 10007.-Ten (10) projectors shall be selected from each lot for test. The lot shall be rejected if any projector fails to initiate seven (7) primers each. The test shall be as specified in 4.4.2. (destructive).

4.3.3.3 Aircraft vibration (see 3.5) - Major defect - Code No. 10008.-Ten (10) projectors shall be selected from each lot for test. The lot shall be rejected if any projector fails to initiate seven (7) primers each. The test shall be as specified in 4.4.3. (destructive).

4.3.3.4 Embrittlement of spring (see 3.6) - Major defect - Code No. 09005.-Fifty (50) springs shall be selected from each heat treatment lot for test. If one or more springs fail to comply with the requirements, the heat treatment lot shall be rejected. The test shall be as specified in 4.4.4. Springs used for this

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

test shall not be returned to the lot. (destructive).

4.3.3.5 Moisture content of packing material (see dwg. 9234284) - Major defect - Code No. 11005.-The contractor shall provide adequate controls to insure compliance with the requirements, and shall test for verification at least one sample of each material from each eight hours production. If the moisture content of a sample exceeds the requirement, and packing has not begun, that quantity of material represented by the sample shall be rejected. If assemblies have been packed with material containing excessive moisture, the remaining material that is represented by the sample together with all assemblies packed with the non-conforming material shall be rejected. The test shall be performed as specified in 4.4.5. (destructive).

4.3.3.6 Heat seal of packing bag (see dwg. 9234284) - Major defect - Code No. 12005.-Ten (10) sealed packages shall be selected from each lot for test. If any heat seal fails to comply with the requirements, the lot shall be rejected. The test shall be as specified in 4.4.6.

4.3.4 Inspection equipment.-Equipment Tabulation Number ET-9229014 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. Those equipment lists coded with the letter "F" on the ET require the contractor to supply designs for inspection equipment as specified in 6.3.

4.3.4.1 Government rights to documentation.-Inspection equipment drawings and lists provided and revised in accordance with the requirements of the ET may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.4 Test methods and procedures

4.4.1 Functioning.-The projector shall be tested by placing the firing pin of the projector in the safe position, inserting the test plug and then releasing the firing pin. A maximum of two (2) attempts may be made to fire the primer. Observation shall be made for compliance with the applicable requirement.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

4.4.2 Salt fog.-The projector shall be subjected to the salt fog specified in MIL-STD-810, Method 509, procedure I for a fifty (50) hour period. The projector shall meet the requirements of 3.3 after this test.

4.4.3 Aircraft vibration.-The projector shall be subjected to the vibration specified in MIL-STD-810, Method 514, procedure X an ambient temperature. The projector shall meet the requirements of 3.3 after this test.

4.4.4 Embrittlement of spring.-The springs shall be stretched to the minimum point of permanent distortion by any method approved by the procuring activity.

4.4.5 Moisture content of packing material.-The moisture content shall be determined in accordance with MIL-STD-1234, Method 102.1, except that a 10 gram sample shall be used and dried for two (2) hours.

4.4.6 Heat seal of packing bag.-The test shall be performed in accordance with the procedure specified in MIL-P-116. After test the seal shall be examined for compliance with the requirements.

5. PREPARATION FOR DELIVERY

5.1 Preservation and packaging

5.1.1 Level A.-The projector assemblies shall be preserved and packaged in accordance with dwg. 9234284.

5.2 Packing

5.2.1 Level A.-The projector assemblies shall be packed in accordance with dwg. 9234285.

5.3 Marking.-The wooden box shall be marked as specified on dwg. 8796522.

6. NOTES

6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.
b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

c. Provisions for submission of first article samples.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government. These code numbers are also used to correlate the characteristics cited on Equipment Lists with the inspections listed in this specification. In addition, they should be cited as references on drawings of equipment designs submitted by the contractor to the Government for approval (see 6.3.3).

6.3 Inspection Equipment Designs.-Inspection equipment designs are to two types - Government Special Inspection Equipment (SIE) designs and contractor designs. SIE designs are designated by drawing numbers on the Equipment Lists referenced on the Equipment Tabulation. Design responsibility for all other inspection equipment is assigned to the contractor. Equipment to be designed by the contractor is designated "CD". The contractor need not furnish any design when a complete Government SIE design is provided. Unless otherwise specified, however, the contractor may submit alternate or modified contractor designs of SIE in accordance with 6.3.2 and 6.3.3 should he elect to do so.

6.3.1 SIE designs.-SIE designs may consist of any of the following:

a. Detailed drawings which completely depict all information necessary for the fabrication and use of the item of inspection equipment.

b. A source control drawing or a specification control drawing as defined in MIL-STD-100.

c. An envelope drawing, as defined in MIL-STD-100, which establishes the criteria which a detail design shall meet. When envelope drawings are specified, the contractor shall prepare designs which comply with the criteria therein.

6.3.2 Contractor designs.-Contractor designs are required for all inspection equipment for which SIE designs are not specified and may include commercial equipment which the contractor proposes to use. (Commercial equipment is defined as unmodified equipment which is cataloged and available for purchase by the general public.) Contractor designs shall include appropriate operating instructions, calibration procedures and maintenance procedures. Commercial equipment shall be fully described by catalog listings or other means which provide sufficient information to permit identification and evaluation by the Government

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.

and may include illustrations and engineering data. Designs shall be prepared for any special fixture(s) required to be used with commercial equipment, or with SIE designs if not otherwise covered thereby (see 6.3.1c). Designs shall be of the category and form (per MIL-D-1000) specified in the Contract Data Requirements Lists (DD Form 1423). The contractor is referred to MIL-HDBK-204, "Inspection Equipment Design" for guidance. The specification number and the applicable five-digit defect code number (or other specific identifying information) from Section 4 of this specification shall be referenced on each contractor design together with the component or assembly drawing number and revision letter to which the specific design applies.

6.3.3 Submission of designs for approval.-Contractor designs shall be approved by the Government prior to fabricating or procuring the equipment. Designs shall be submitted for approval to Picatinny Arsenal, ATTN: SMUPA-QA-A-M, Dover, New Jersey, 07801 in accordance with the stipulations, time frame and distribution specified in the contract Data Requirements List (DD Form 1423) or in the contract. Partial submission of inspection equipment designs is permissible and encouraged. However, the completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will normally be accomplished within one month after receipt.

6.4 This specification supersedes PA-PD-3117 dated 17 February 1969.

Custodian:
Army-MU

Preparing activity:
Army-MU

Project Number: 1370-A-001

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T19:14Z
Check the source to verify that this is the current version before use.