MILITARY SPECIFICATION

FUZE, MT, SQ, M577
LOADING, ASSEMBLING, PACKING AND METAL PARTS
FUZE, MT, SQ, M582 METAL PARTS

This amendment forms a part of Military Specification MIL-F-50983B (AR), dated 30 June 1980, and is approved for use by the US Army Armament Research and Development Command and is available for use by all Departments and Agencies of the Department of Defense.

PAGE 6

4.3.1: To the group entitled 15 each, delete: "9236518".

4.3.1: To the group entitled 15 each, add: "9236729, 9236730 and 9236731".

PAGE 7

4.3.1: To the group entitled 50 each, Add "9236712, 9236733".

PAGE 45

4.4.2.36, to the block entitled Drawing Number: Add: "9236712 and 9236733".

To the block entitled Next Higher Assembly: Add "9236711 and 9236732".

PAGE 46

4.4.2.37, to the block entitled Drawing Number: Add "9236732".

Add:

Category	Examination	No. of Sample Units	AQL or 100%	Reqmt. Para.	Para. Ref. Insp Method
"112	9lb. axial load	d	e	3.2	4.5.1ae".

Note b: Add: "and 9236742".

Note c: Add: "and 9236732".

FSC 1390

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:46Z
Check the source to verify that this is the current version before use.

4.4.2.37, to block entitled Notes: Add "d. Destructive. See paragraph 4.4.3.7 for applicable sample plan."

4.4.2.37, to block entitled Notes: Add "e. Reject the Timer Assembly inspection lot if one (1) or more defective units are found."

PAGE 73

* 4.4.2.64, to block entitled Drawing Number: Delete "9236575" and substitute "9345286".

PAGE 78

* 4.4.2.68, to block entitled Drawing Number: Delete "9236562" and substitute "9345287".

* 4.4.2.68: Add

Category	Examinations	No. of Sample Units	AQL or 100%	Req'mt Para.	Para Ref Insp. Method
"105	Height of ribs		0.40%	3.2	Gage".

PAGE 79

* 4.4.2.69: Delete in its entirety.

PAGE 80

* 4.4.2.70: Add

Category	Examination	No. of Sample Units	AQL or 100%	Req'mt Para.	Para. Ref. Insp. Method
"103	Detonator(s) missing or inverted		0.40%	3.2	Visual
104	Crimp missing over detonator holder		0.40%	3.2	Visual
			0.40%	3.2	Visual
105	Tape missing		0.40%	3.2	Visual
106	Detonator(s) not positioned over MDF		0.65%	3.2	Visual"

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:46Z
Check the source to verify that this is the current version before use.

PAGE 97

4.4.2.87, to the block entitled Title: Delete "Element, Crush" and substitute "Plug, Retainer".

To the block entitled Drawing Number: Delete "9236518" and substitute "9236731".

To the block entitled Next Higher Assembly: Delete "9236516" and substitute "9236729".

To the block entitled Examination or Test: Delete "Static Load Test" and substitute "Outside diameter".

To the block entitled No. of Sample Units: Delete "40a".

To the block entitled AQL or 100%: Delete "b" and substitute "0.40%".

To the block entitled Paragraph Reference/Inspection Method: Delete "4.5.1f" and substitute "Gage".

To the block entitled Notes: Delete Note a and Note b in their entirety.

PAGE 98

4.4.2.88, to the block entitled Drawing Number: Delete "9236516" and substitute "9236729".

To the block entitled Examination or Test: Delete "Crush retainer missing" and substitute "Plug retainer missing".

To the block entitled Examination or Test: Delete: "Crush element missing" and substitute "Axial static load test".

Major 102, to the block entitled No. of Sample Units: Add "40a".

To the block entitled AQL or 100%: Delete: "0.40%" and substitute: "b".

To the block entitled Paragraph Reference/Inspection Method: Delete "Manual" and substitute: "4.5.1.f".

To the block entitled Notes: Add "a. Destructive".

To the block entitled Notes: Add "b. Reject the lot if one (1) or more defective units are found."

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:46Z
Check the source to verify that this is the current version before use.

PAGE 112

Add: "4.4.3.7 Axial load test. The Timer Hair-spring and Timer Support and Pivot Assembly samples selected for the azial load test shall be randomly selected from each batch used to assemble the Timer Assembly inspection lot. One sample shall be welded at the beginning of the Timer Assembly inspection lot manufacturing period, two samples shall be welded at random times during the period and one sample at the end of the same period. The samples shall contain the number of welds specified on drawing 9236711 and shall be welded on the equipment used to manufacture the Timer Assembly inspection lot using the same equipment lot using the same equipment parameters (tip, frequency, pressure and energy). The equipment parameters used during an inspection lot manufacturing period shall be recorded. If prior to welding the required number of test samples, the inspection lot manufacturing period is interrupted and can not be continued on the same equipment with the same parameters. Timer Assemblies shall be selected from the inspection lot as test samples. The last Timer Assembly of the inspection lot manufacturing period shall be selected and, if necessary, Timer Assemblies shall be randomly selected from the same period. A Timer Assembly inspection lot shall consist of a maximum of two (2) hours production and manufactured on the same equipment and the same equipment parameters".

PAGE 114

4.5.1, Table I, subparagraph f: Delete "Crush Element (Dwg. 9236518)" and substitute "Setting Key Assembly (Dwg. 9236729)".

PAGE 116

* 4.5.1, Table I, subparagraph s: Delete in its entirety.

PAGE 117

4.5.1, Table I, subparagraph ab: Add "9236733".

Table I, subparagraph ac: Add "9236733".

* Table I, subparagraph ad: Add "9236733".

Table I, subparagraph ae: Add "9236733".

* Table I, subparagraph ae: Delete "9236712".

PAGE 121

4.5.2, Table II, subparagraph d: Add "9236733".

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:46Z
Check the source to verify that this is the current version before use.

4.5.21.3.4; second and third line: Delete "and the suspect value falls outside the function time limits".

The margins of this amendment are marked with an asterisk to indicate where changes (additions, modifications, corrections, deletions) from the previous amendment were made. This was done as a convenience only and the Government assumes no liability whatsoever for any inaccuracies in these notations. Bidders and contractors are cautioned to evaluate the requirements of this document based on the entire content irrespective of the marginal notations and relationship to the last previous amendment.

Custodian:
Army - AR

Preparing activity:
Army - AR

(Project 1390-A315)

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T20:46Z
Check the source to verify that this is the current version before use.