MIL-D-45473B(MU)
30 APRIL 1965

SUPERSEDING
MIL–D–45473A (ORD)
24 AUGUST 1961

MILITARY SPECIFICATION

# DEMOLITION KIT, PROJECTED CHARGE, M157 LOADING, ASSEMBLING AND PACKING

## 1. SCOPE

1.1 This specification covers the loading, assembling and packing of Explosive Fuze Container Loading Assembly, Impact Fuze Section Loading Assembly, and Center Section Loading Assembly for one type of demolition kit designated as Demolition Kit, Projected Charge, M157.

## 2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids or request for proposal, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL–A–2550 — Ammunition and Special Weapons; General Specification for.

MIL–I–45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL–STD–105 — Sampling Procedures and Tables for Inspection by Attributes. (ABC–STD–105.)

MIL–STD–109 — Quality Assurance Terms and Definitions.

MIL–STD–1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

DRAWINGS

ORDNANCE CORPS

8836910 — Demolition Kit, Projected Charge, M157, Installation Drawing.

8836933 — Explosive Fuze Container Loading Assembly.

8836944 — Impact Fuze Section Loading Assembly.

8836946 — Center Section Loading Assembly.

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

8837997 — Box, Packing, Ammunition, for Impact Fuze Section Assy for Demolition Kit, Projected Charge, M157.

8838000 — Box, Packing, Ammunition, for Explosive Fuze Container Loading Assy for Demolition Kit, Projected Charge, M157.

8838001 — Protector, End, Packing, for Body Section Assy and Center Section Assy for Demolition Kit, Projected Charge, M157.

## PUBLICATIONS

ORDNANCE CORPS

IEL–9200256 — Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

## 3. REQUIREMENTS

**3.1 Material.** Materials and parts shall be in accordance with applicable drawings and specifications.

**3.2 Assemblies.** The center section loading assembly, impact fuze loading assembly and explosive fuze container loading assembly shall comply with all requirements specified on Drawing (dwgs.) 8836946, 8836944 and 8836933 and with all requirements specified in applicable specifications.

**3.3 Functioning.**

**3.3.1** *Center section loading assembly, impact fuze section assembly and explosive fuze container loading assembly.* The center section loading assembly, impact fuze section assembly and explosive fuze container loading assembly shall function properly. Proper functioning shall be defined as propagation of the fuze section to the center section and subsequent detonation of the center section.

**3.4 Workmanship.** The loading cavities of the parts and the loaded assemblies shall be loaded and assembled in a thorough, workmanlike manner. The parts shall be clean and free of rust, corrosion products, and other foreign matter. The cleaning method used shall not be injurious to any part nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few slight scratches not exposing base material. All required marking shall be neat and sharply defined.

## 4. QUALITY ASSURANCE PROVISIONS

**4.1 General quality assurance provisions.** Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. Reference shall be made to MIL–STD–109 in order to define terms used herein. The provisions of MIL–A–2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance, the contractor shall supply the following information accompanied by a certificate which attests that the information provided is correct and applicable to the product being submitted:

(a) A statement that the lot complies with all quality assurance provi-



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

sions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspection performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

(e) Certificates of conformance on all material purchased by the contractor when such material is controlled by Government specifications referenced in any of the contractual documents.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified "critical" be accepted solely on the basis of the contractor's records.

**4.2 Initial production inspection.**

4.2.1 *Submission.* The contractor, prior to initiation of regular production, shall submit an initial production sample to a Government approved facility as designated by the contracting officer (see 6.4) for testing in accordance with the provisions of 4.2.2. The initial production sample shall consist of two (2) sets, each set consisting of one loaded center section, one loaded impact fuze section and loaded explosive fuze container and equal quantities of Fuze, Mine, AT, M603; which have been produced by the contractor or furnished by a supplier and which has been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of conformance for materials. An initial production sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply such as to significantly affect product uniformity as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure that it conforms to the requirements of the contract and submit a record of this inspection with the sample. A sample containing known defects will not be submitted unless specifically authorized by the contracting officer.

4.2.2 *Inspection to be performed.* The assemblies and components shall be inspected for conformance with any or all of the requirements of this specification and any or all of the requirements of the applicable drawings.

4.2.3 *Rejection.* If any assembly or component fails to comply with any or all of the applicable requirements, the initial production sample shall be rejected. The Government reserves the right to terminate its in-



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

spection upon any failure of a component in the sample to comply with any or all of the stated requirements. In the event of rejection, the Government reserves the right to require the contractor to take corrective action and submit a new initial production sample or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the Contracting Officer.

**4.3 Inspection provisions.**

4.3.1 *Lot formation.* A lot shall consist of demolition kit sub-assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance or fit, as determined by the Government shall not necessitate changing the lot interfix number. Lots shall be submitted for inspection in accordance with MIL–STD–105 (or MIL–STD–1235, when applicable). Each lot shall contain:

(a) Metal parts or metal parts sub-assemblies from not more than one lot interfix number from one manufacturer.

(b) Fuzes from not more than one lot interfix number from one manufacturer.

(c) Boosters from not more than one lot interfix number from one manufacturer.

(d) Composition B from not more than one lot interfix number from one manufacturer.

(e) Composition C–4 from not more than one lot interfix number from one manufacturer.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with MIL–STD–105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with MIL–STD–1235 may be used, for defects other than critical, if approved by the procuring activity. Also, at the option of the procuring activity, AQL's and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Explosive fuze container, prior to loading (see dwg. 8836933).

| *Categories* | *Defects* | *Method of inspection* | *Code No. (see 6.2)* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Foreign matter on interior surface | Visual | 01001 |
| 102. | Bare spots in protective coating on interior surface | Visual | 01002 |
| Minor: None defined. | | | |

4.3.2.2 Explosive fuze container, prior to assembling cap (see dwg. 8836933).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Booster missing | Visual | 02001 |
| 102. | Booster retainer ring missing or not seated properly | Visual | 02002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship (see 3.4) | Visual | 02003 |



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

4.3.2.3 Explosive fuze container loading assembly (see dwg. 8836933).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 0.65 percent | | |
| 101. | Assembly damaged | Visual | 03001 |
| 102. | Loading plug loose or not properly seated | Visual | 03002 |
| 103. | Cap missing | Visual | 03003 |
| Minor: | AQL 1.50 percent | | |
| 201. | Coating missing or inadequate (except for slight scratches) | Visual | 03004 |
| 202. | Marking missing, misleading or unidentifiable | Visual | 03005 |
| 203. | Evidence of poor workmanship, (see 3.4) | Visual | 03006 |

4.3.2.4 Center section and impact fuze, section, prior to loading (see dwg. 8836946 and 8836944).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Foreign matter on interior surface of charge cavity | Visual | 04001 |
| 102. | Bare spot in protective coating on interior surface | Visual | 04002 |
| Minor: | AQL 0.65 percent | | |
| 201. | Evidence of poor workmanship, (see 3.4) | Visual | 04003 |

4.3.2.5 Center section loading assembly and impact fuze section assembly (see dwgs. 8836946 and 8836944).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 1.00 percent | | |
| 101. | Depth of charge, minimum | Gage | 05001 |
| 102. | Impact fuze bullet assembly missing (8836944 only) | Visual | 05002 |
| 103. | Insert tube lid missing | Visual | 05003 |
| 104. | Insert tube lid loose or not seated properly | Manual | 05004 |
| 105. | Caked explosive on exterior | Visual | 05005 |
| Minor: | AQL 1.50 percent | | |
| 201. | Bare spots in protective coating (except for slight scratches) | Visual | 05006 |
| 202. | Marking missing, misleading or unidentifiable | Visual | 05007 |
| 203. | Dummy container missing (8836944 only) | Visual | 05008 |
| 204. | Evidence of poor workmanship (see 3.4) | Visual | 05009 |

4.3.2.6 Box, prior to sealing (see dwg. 8838001, 8837997, and 8838000).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | AQL 0.40 percent | | |
| 101. | Component missing | Visual | 06001 |
| 102. | Component incorrectly packed | Visual | 06002 |

Minor: None defined.



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

**4.3.2.7** Box, packing sealed (see dwg. 8838001, 8837997 and 8838000).

| *Categories* | *Defects* | *Method of inspection* | *Code No.* |
|---|---|---|---|
| Critical: None defined | | | |
| Major: | **AQL 1.00 percent** | | |
| 101. | Bor broken or split to extent of exposing component | Visual | 07001 |
| 102. | Strapping missing, loose, or wrong type | Visual | 07002 |
| 103. | I.C.C. nomenclature missing or misleading | Visual | 07003 |
| 104. | Hardware loose, missing, or damaged | Visual | 07004 |
| 105. | Contents loose | Manual | 07005 |
| Minor: | **AQL 1.50 percent** | | |
| 201. | Marking misleading, missing or unidentifiable | Visual | 07006 |
| 202. | Strapping not equally spaced | Visual | 07007 |
| 203. | Skids missing or damaged (if applicable) | Visual | 07008 |

**4.3.3** *Testing.*

**4.3.3.1** *Functioning (see 3.3)—Major defect—Code No. 08001.* After the initial production sample has successfully met the criteria of 4.2.2, a sample of one set shall be selected thereafter from each lot consisting of 1 to 34 sets and a sample of two sets from each lot consisting of 35 or more sets. The test shall be performed as specified in 4.4.1. If one or more sets fail to meet the specified requirement, the lot shall be rejected.

4.3.4 *Inspection Equipment.* Index of Inspection Equipment Number IEL–9200256 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement of parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and wherever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with MIL–I–45607.

4.3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available to the Government all inspection and test equipment necessary for determining conformance with contract requirements. Personnel for operating the equipment and verification of its accuracy shall be supplied by the contractor for the performance of examination or test by the Government.

**4.4 Test methods and procedures.**

4.4.1 *Functioning.* The explosive fuze container, with fuze assembled shall be assembled as required by details A and B of dwg. 8837910. The center section shall be assembled to the male connector end of the impact fuze section and the assembly fired upon from a distance of approximately 100 feet using a round from a U.S.M14 rifle. The cross-marked fuze housing door shall be the target. Observation shall be made for lack of propagation between the impact fuze and center sections and complete detonation of the center section. Any set not propagating the detonating fully shall be classed defective.

## 5. PREPARATION FOR DELIVERY

**5.1 Preservation, packing and marking.**



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

5.1.1 *Level A.* Preservation, packing and marking of the assemblies shall be in accordance with dwgs. 8837997, 8838000 and 8838001, as applicable.

5.1.2 *Demolition kit.* A complete demolition kit shall be composed of the following units with applicable packing:

| *Quantity of units and containers* | *Unit* | *Unit Dwg. No.* | *Packing Dwg. No.* |
|---|---|---|---|
| 62 | Center section loading assembly | 8836946 | 8838001 |
| 13 | Body section assembly | 8838126 | 8838001 |
| 1 | Nose section assembly | 8838124 | 8837998 |
| 1 | Tail section assembly | 8838152 | 8837999 |
| 2 | Impact fuze loading assembly | 8836944 | 8837997 |
| 2 | M603 fuzes and explosive fuze containers | 8836933 | 8838000 |

**5.2 Data cards.** Data cards shall be prepared for each lot in accordance with the information specified in MIL–A–2550.

## 6. NOTES

**6.1 Ordering data.** Procurement documents shall specify title, number and date of this specification.

**6.2 Inspection code numbers.** The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

**6.3 Inspection equipment.** The contractor shall design inspection equipment as required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF — Contractor's design responsibility on Army format in accordance with MIL–D–45608.
CDCF — Contractor's design responsibility on contractor format.
AD — Army design.
ADMU — Army design, mandatory for use.
CE — Commercial equipment.
SCD — Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may,



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.

however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black line on white background and shall provide a legible print produced via the 35MM microfilm process. Contractor shall submit one copy of the final design as a rolled set or flat set.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

**6.4 Submission of Initial Production Sample.** Instructions, as to the location for the evaluation of initial production sample, shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to Commanding Officer, Picatinny Arsenal, ATTN: SMUPA–NI.

**Custodian:**
**Army—MU**

**Preparing activity:**
**Army—MU**
**Project No. 1375–A909**



Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:06Z
Check the source to verify that this is the current version before use.