MIL-D-45473B (MU)
AMENDMENT 1
23 July 1966

MILITARY SPECIFICATION

DEMOLITION KIT PROJECTED CHARGE, M157
LOADING, ASSEMBLING AND PACKING

This Amendment forms a part of Military Specification MIL-D-45473B (MU), dated 30 April 1965, which has been prepared and used for procurement by the Department of the Army.

Paragraph 2.1 Delete, "Ordnance Corps" substitute, "U.S. Army Munitions Command."

Add: "2.2 Other Publications.-The following document forms a part of this specification to the extent specified herein. Unless indicated, the issue in effect on date of invitation for bids shall apply."

Code of Federal Regulations

49 CFR 71-90 - Interstate Commerce Commission Rules and Regulations for Transportation of Explosives and Other Dangerous Articles.

(The Interstate Commerce Commission Regulations are now a part of the Code of Federal Regulations (1949 edition - revised 1950) available from the superintendent of documents, Government Printing Office, Washington 25, D.C. Orders for the above publication should cite "49 CFR 71-90 (latest revisions)".

Add: to paragraph 2.1 under Standards, Military:

"MIL-STD-1167 - Ammunition Data Cards."

Paragraph 4.1.1 In sub-paragraph "e", add after the words "...controlled by Government..." the words "or commercial".

Paragraph 4.3.1, delete in its entirety and substitute:

"4.3.1 Lot formation.-The term "lot" as used throughout this specification refers to an inspection lot, which is defined as an essentially homogeneous collection of units of product from which a representative sample is drawn and inspected to determine conformance of the lot with applicable requirements.

FSC 1375

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.

The sample selected shall represent only that quantity of units from which the sample was drawn and shall not be construed to represent any prior or subsequent quantities presented for inspection. Homogeneity shall be considered to exist provided the lot has been produced by one manufacturer, in one unchanged process, in accordance with the same drawing, specification, or revision thereof. Changes to either the process, specification, or drawing not affecting safety, performance, interchangeability, or storage, as determined by the Government inspector, shall not be deemed to alter the homogeneity of the lot. Each lot of demolition kits shall contain:

a. Metal parts or metal parts sub-assemblies from not more than one lot interfix number from one manufacturer.

b. Fuzes from not more than one lot interfix number from one manufacturer.

c. Boosters from not more than one lot interfix number from one manufacturer.

d. Composition B from not more than one lot interfix number from one manufacturer.

e. Composition C-4 from not more than one lot interfix number from one manufacturer.

Inspection lots shall comply with MIL-STD-105 and shall be numbered in accordance with MIL-STD-1168.

Unless otherwise approved by the contracting officer, the inspection lot size of major assemblies or end items deliverable under the contract shall be not less than the smallest weekly estimate of quantities contractually scheduled for production during the contract period nor more than the largest quantity contractually scheduled for delivery during any month of the contract period. Inspection lots for components or sub-assemblies, other than the items of delivery, shall be homogeneous and of a size convenient to the contractor.

Paragraph 4.3.2.5, Minor 201, delete: "(except for slight scratches)" and substitute: "(except bottom of assembly exceeding 1/16 square inch)".

Paragraph 4.3.3.1, Delete in its entirety and substitute:

"Functioning (see 3.3) - Major defect - Code No. 08001.- A sample of one set shall be selected from a lot consisting of 1 to 34 sets or a sample of two sets from a lot consisting of 35 or more sets. The test shall be performed as specified in 4.4.1 for five consecutive lots. If one or more sets fail to meet the specified requirement in any one of the five lots, testing shall then be continued until five consecutive lots are accepted, after

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.

which time, testing may be stopped except that a sample will be selected from some future lot and tested. Should this sample fail, the lot shall be rejected and testing will revert to lot by lot basis until five consecutive lots are accepted.

Paragraph 5.2, delete in its entirety.

Paragraphs 6.1 through 6.3.7 delete in their entirety and substitute:

"6.1 Ordering data.-Procurement documents shall specify the following:

a. Title, number and date of this specification.

b. Data cards.-Data cards shall be prepared for each lot in accordance with the information specified in Standard MIL-STD-1167.

6.2 Inspection code numbers.-The five digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment.-The contractor shall design inspection equipment as required by the referenced inspection Equipment Lists (EL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 Inspection equipment lists.-Inspection equipment lists indicate the availability of inspection equipment designs by showing in the "number" column of the list of inspection equipment (SMUPA Form 1010) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as "Contractor Design" in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 Inspection equipment list codes.-The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the EL by the following codes:

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.

CDAF - Contractor's design responsibility on Army format in accordance with MIL-D-45608.
CDCF - Contractor's design responsibility on contractor format.
AD - Army design.
ADMU - Army design, mandatory for use.
CE - Commercial equipment.
SCD - Specification control drawing.

6.3.3 Army designs.-Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs (see 6.3.6) or commercial equipment selections (see 6.3.5) must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 Specification control drawing.-Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagrammatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings must be described in sufficient detail to permit identification and evaluation by the Government (see 6.3.5). Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 Commercial equipment.-Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors normally are not required to furnish drawings of

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.

commercial inspection equipment, but a list of such equipment must be approved by the Government. When commercial inspection equipment requires the use of special fixturing, the design of this fixturing shall be considered as part of the total design, and 6.3.6 shall apply. In the latter case, only those portions of the commercial equipment need be detailed in the designs as are necessary to completely fabricate, calibrate, and operate the total item of inspection equipment. Lists and fixturing designs shall be submitted for approval as specified in 6.3.7.

6.3.6 Contractor designs.-Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL-D-45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35mm microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set. Designs shall be submitted for approval as specified in 6.3.7.

6.3.7 Submission of contractor designs.-Unless otherwise specified on the EL, all designs of equipment for inspection of defects classified as critical and major shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN: SMUPA-ND. All other designs of inspection equipment shall be approved by the inspection element of the agency administering the contract; submission shall be as directed by the Contracting Officer. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs. Picatinny Arsenal design review will be accomplished normally within one month after receipt.

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.

MIL-D-45473B (MU)

Add the following paragraph:

"6.5 Submission of test data and ammunition data cards.- In addition to the normal distribution of records, for loaded items procured by the Department of the Army, one copy of all ballistic test data and ammunition data cards shall be forwarded to the following:

Commanding Officer
Picatinny Arsenal
Dover, New Jersey
ATTN: SMUPA-ND5
SMUPA-DC"

Custodian:
Army-MU

Preparing activity:
Army-MU

Project No. 1375-A1029

Source: https://assist.dla.mil -- Downloaded: 202610-22T03:06Z
Check the source to verify that this is the current version before use.