MIL-W-45466E (MU)
30 DECEMBER 1965
SUPERSEDING
MIL-W-45466D (MU)
8 JULY 1963

MILITARY SPECIFICATION

WARHEAD, GUIDED MISSILE HE, XM5E5 PARTS FOR

1. SCOPE

1.1 This specification covers quality assurance provisions, and special requirements not covered by the drawings, for the fabrication of the inert parts for one type of warhead designated as Warhead, Guided Missile, HE, XM5E5.

2. APPLICABLE DOCUMENTS

2.1 The following documents of the issue in effect on date of invitation for bids, or request for proposals, form a part of this specification to the extent specified herein:

SPECIFICATIONS

MILITARY

MIL-A-2550 — Ammunition and Special Weapons, General Specification for.

MIL-I-45607 — Inspection Equipment, Supply and Maintenance of.

STANDARDS

MILITARY

MIL-STD-105 — Sampling Procedures and Tables for Inspection by Attributes.

MIL-STD-109 — Inspection Terms and Definitions

MIL-STD-1235 — Single and Multilevel Continuous Sampling Procedures and Tables for Inspection by Attributes.

FEDERAL

FED. TEST METHOD STD. NO. 151 — Metals; Test Methods.

DRAWINGS

ORDNANCE CORPS

8861584 — Warhead, XM5E5, Inert Parts Assembly

8830879 — Crate, Packing, Ammunition, Dual, for Warhead Guided Missile, HE, XM5E5, XM9E3 or Warhead, Guided Missile, Inert, XM10E3.

FSC 1336

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

8837892 — Crate, Packing Ammunition, Single, for Warhead, Guided Missile, HE, XM5, XM9, or Warhead, Guided Missile, Inert, XM10.

PUBLICATIONS

ORDNANCE CORPS

IEL–8861584 — Index of Inspection Equipment Lists.

(Copies of specifications, standards, drawings and publications required by suppliers in connection with specific procurement functions should be obtained from the procuring activity or as directed by the contracting officer.)

3. REQUIREMENTS

3.1 Material. Materials shall be in accordance with applicable drawings and specifications.

3.2 Inert parts assemblies. The inert parts assemblies shall comply with all requirements specified on Drawing (dwg.) 8861584, and with all requirements specified in applicable specifications.

3.3 Leakage test of inert parts assembly. The inert parts assembly shall withstand an internal air pressure test of 2.0 pounds per square inch, minimum, for 60 seconds, minimum, with no evidence of leakage.

3.4 Workmanship.

3.4.1 *Molded parts.* The molded parts shall be free of porosity, warpage in excess of drawing dimensions, checks, cracks, chipped edges, blisters, scratches, and other defects which would affect their serviceability. Small chips at the end of machined cavities will be disregarded.

3.4.2 *Foreign matter.* All parts shall be free of chips, dirt, grease, excess flash, rust, silicone products and other foreign material. The cleaning method shall not be injurious to any of the parts nor shall the parts be contaminated by the cleaning agent. Surface coatings shall be continuous except for a few slight scratches not exposing base material. All marking shall be neat and sharply defined.

4. QUALITY ASSURANCE PROVISIONS

4.1 General quality assurance provisions. Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commercial laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements. References shall be made to Standard MIL–STD–109 in order to define terms used herein. The provisions of Specification MIL–A–2550 shall apply.

4.1.1 *Submission of product.* At the time the completed lot of product is submitted to the Government for acceptance the contractor shall supply the following information accompanied by a certificate which attests that the information provided is cortests that the information provided is corsubmitted:

(a) A statement that the lot complies with all of the quality assurance provisions specified within this specification.

(b) Number of units of product inspected.

(c) Results obtained, by defect code, for all inspections performed.

(d) Drawing, specification number and date, together with an identification and date of changes.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

(e) Certificates of conformance on all material purchased by the contractor when such material is controlled by Government or commercial specifications referenced in any of the contractual documents. A certificate covering the glass cloth for cover, dwg. 8800961, need not be furnished except with the initial production sample.

(f) Number of items in the lot.

(g) Date submitted.

The certificate shall be signed by a responsible agent of the certifying organization. The initial certificate submitted shall be substantiated by evidence of the agent's authority to bind his principal. Substantiation of the agent's authority will not be required with subsequent certificates unless, during the course of the contract, this authority is vested in another agent of the certifying organization.

4.1.2 *Government verification.* Using the contractor's written quality assurance procedure, this detail specification, the applicable drawings and other contractual documents as a guide, the Government inspector shall verify at unscheduled intervals all quality assurance operations performed by the contractor. Verification will be performed to the extent necessary to assure compliance with the contractual requirements. Severity of Government inspection of individual characteristics will be directly related to the seriousness of the classification assigned. In no instance will a characteristic classified critical be accepted solely on the basis of the contractor's records.

4.2 Initial production.

4.2.1 *Submission.* Prior to regular production, the contractor shall submit an initial production sample to a Government-approved facility, as designated by the contracting officer (see 6.6), for evaluation in accordance with the provisions of 4.2.2. The sample shall consist of 2 assemblies and 4 complete sets of parts (i.e., 4 each of every component, except fragments, 20 of which shall be submitted, and 4 each of every subassembly) which have been produced by the contractor, or furnished by a supplier, and which have been manufactured using the same production processes, procedures and equipment which will be used in fulfilling the contract. All parts and materials, including packaging and packing, shall be obtained from the same sources of supply as will be used in regular production. The sample shall be accompanied by certificates of analysis or test, as applicable, or both for materials. An initial production sample, or portion thereof, as directed by the contracting officer, shall also be submitted whenever there is a lapse in production for a period in excess of 90 days, or whenever a change occurs in manufacturing process, material used, drawing, specification or source of supply as to significantly affect product uniformity, as determined by the Government. Prior to submission, the contractor shall inspect the sample to the degree necessary to assure it conforms to the requirements of the contract and submit a record of this inspection with the sample.

4.2.2 *Inspections to be performed.* Each assembly, sub-assembly and component shall be examined by the Government for all requirements and dimensions of applicable drawings. In addition, the sample will be submitted to the applicable examinations of 4.3.3.1.

4.2.3 *Rejection.* If any assembly, subassembly or component fails to comply with an applicable requirement, the initial production sample shall be rejected. The Government reserves the right to terminate its inspection upon any failure of an assembly, subassembly or component in the sample to comply with any of the stated requirements. In the event of rejection, the Government reserves the right to require the

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

contractor to take corrective action and submit a new initial production sample, or portion thereof. Until an initial production sample is accepted, the contractor is, in no way, authorized by the Government to initiate regular production unless otherwise directed by the contracting officer.

4.3 Inspection provisions.

4.3.1 *Lot formation.* A lot shall consist of inert parts assemblies produced by one manufacturer in one unchanged process, in accordance with the same drawing, same drawing revision, same specification, and same specification revision. Drawing, specification, and process changes not affecting safety, performance, or fit, as determined by the Government, shall not necessitate changing the lot interfix number.

4.3.2 *Examination.* Sampling plans and procedures for the following classifications of defects shall be in accordance with Standard MIL–STD–105 except that inspection for critical defects, when listed, shall be 100 percent. Continuous sampling plans in accordance with Standard MIL–STD–1235 may be used if approved by the procuring activity. Also, at the option of the procuring activity, AQL and sampling plans may be applied to the individual characteristics listed using an AQL of 0.40 percent for each major defect and an AQL of 0.65 percent for each minor defect. Once agreement has been reached as to which method will be used (group or individual) that method will be used for all of the CD listed in this specification. Equipment necessary for the performance of the inspections listed shall be in accordance with 4.3.4.

4.3.2.1 Insert, forward (see dwg. 8800268 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No. (see 6.3)*
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Pitch diameter of internal thread	Gage	01001
102.	Major diameter of external thread, minimum (min.)	Gage	01002
Minor:	AQL 1.00 percent		
201.	Operation missing	Visual	01003
202.	Evidence of poor workmanship (see 3.4)	Visual	01004

4.3.2.2 Insert, mounting (see dwg. 8861590 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Pitch diameter of thread	Gage	02001
102.	Thickness of flange	Gage	02002
103.	Diameter over knurl	Gage	02003
104.	Knurl incomplete or not sharp	Visual-Manual	02004

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
Minor:	AQL 1.50 percent		
201.	Minor diameter of thread, maximum (max.)	Gage	02005
202.	Diameter of flange, min.	Gage	02006
203.	Operation missing	Visual	02007
204.	Evidence of poor workmanship (see 3.4)	Visual	02008

4.3.2.3 Insert, aft (see dwg. 8800274 covering a detail of dwg. 8861588).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Diameter of cavity	Gage	03001
102.	Depth of cavity, min.	Gage	03002
Minor:	AQL 1.50 percent		
201.	Chamfer missing	Visual	03003
202.	Knurl missing	Visual	03004
203.	Evidence of poor workmanship (see 3.4)	Visual	03005

4.3.2.4 Insert, liner (see dwg. 8800275 covering a detail of dwg. 8861585).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Pitch diameter of thread	Gage	04001
102.	Diameter over knurl	Gage	04002
103.	Knurl incomplete or not sharp	Visual	04003
Minor:	AQL 1.00 percent		
201.	Minor diameter of thread, max.	Gage	04004
202.	Evidence of poor workmanship (see 3.4)	Visual	04005

4.3.5.2 Plug, closing (see dwg. 8800284 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Thickness, min.	Gage	05001
102.	Component damaged or not flat	Visual	05002

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
Minor:	AQL 0.65 percent		
201.	Foreign matter (see 3.4.2)	Visual	05003

4.3.2.6 Body, inner, forward (see dwg. 8861587 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Sidewall thickness, min.	Gage	06001
102.	Molding defects (see 3.4.1)	Visual	06002
Minor:	AQL 0.65 percent		
201.	Foreign matter (see 3.4.2)	Visual	06003

4.3.2.7 Body, inner, aft (see dwg. 8861588 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.65 percent		
101.	Depth to bottom of cavity in insert, min.	Gage	07001
102.	Sidewall thickness, min.	Gage	07002
103.	Molding defect (see 3.4.1)	Visual	07003
Minor:	AQL 0.65 percent		
201.	Foreign matter (see 3.4.2)	Visual	07004

4.3.2.8 Liner, safety and arming (see dwg. 8861586 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Location of liner inserts	Gage	08001
102.	Depth of pellet cavity, min. (3 places)	Gage	08002
103.	Diameter of pellet cavity, min. (3 places)	Gage	08003
104.	Spring pin projects into S&A cavity	Visual	08004
105.	Inserts above flush	Visual	08005

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

Categories	*Defects*	*Method of inspection*	*Code No.*
106.	Spring pins missing or incompletely filled with resin	Visual	08006
107.	Molding defects (see 3.4.1)	Visual	08007
Minor:	AQL 0.65 percent		
201.	Foreign matter (see 3.4.2)	Visual	08008

4.3.2.9 Liner, safety and arming, tactical (see dwg. 8861585 covering a detail of dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 0.40 percent		
101.	Location and orientation of tube holes	Gage	09001
102.	Diameter of tube holes, min.	Gage	09002
Minor:	AQL 0.65 percent		
201.	Evidence of poor workmanship (see 3.4)	Visual	09003

4.3.2.10 Assembly, warhead, inert parts, prior to painting (see dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Location of mounting inserts	Gage	10001
102.	The plane formed by the centerline of the four mounting holes not perpendicular to centerline of warhead or the plane formed by these centerlines not flat within tolerance specified	Gage	10002
103.	Total length, max.	Gage	10003
104.	Diameter across mounting inserts, max.	Gage	10004
105.	Forward insert above flush	Visual	10005
106.	Mounting flange cracked or damaged	Visual	10006
Minor:	AQL 1.50 percent		
201.	Void not filled	Visual	10007
202.	Outer body improperly applied	Visual	10008
203.	Evidence of poor workmanship (see 3.4)	Visual	10009

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

4.3.2.11 Assembly, warhead, inert parts (see dwg. 8861584).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Weight marked on the assembly incorrect or weight of assembly out of limits	Balance	11001
102.	Air test stamp missing	Visual	11002
103.	Interior coating improper or inadequate i.e., sag, not dry, bare spots etc.	Visual	11003
104.	Paint or foreign matter in threaded holes, aft insert, safety and arming liner or closing plug surface (see 3.4.2)	Visual	11004
105.	Cover cushion missing	Visual	11005
Minor:	AQL 1.50 percent		
201.	Closing plus insecurely taped	Visual-Manual	11006
202.	Exterior coating incomplete, inadequate or improper	Visual	11007
203.	Marking incomplete or incorrect	Visual	11008
204.	Foreign matter (see 3.4.2)	Visual	11009

4.3.2.12 Shipping container, prior to sealing (see dwg. 8830879 or dwg. 8837892).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
101.	Cushioning pad on base missing	Visual	12001
102.	Warhead not seated properly	Visual	12002
103.	Hold down strap missing or insecure	Visual-Manual	12003
Minor:	AQL 0.65 percent		
201.	Foreign matter in container	Visual	12004

4.3.2.13 Shipping container (see dwg. 8830879 or dwg. 8837892).

Categories	*Defects*	*Method of inspection*	*Code No.*
Critical:	None defined		
Major:	AQL 1.00 percent		
101.	Strapping missing, broken, or loose	Visual-Manual	13001
102.	Board broken, split or cracked	Visual	13002
103.	Skid missing or damaged	Visual	13003

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

Categories	Defects	Method of inspection	Code No.
104.	Contents exposed	Visual	13004
105.	Lag screw missing	Visual	13005
Minor:	AQL 1.50 percent		
201.	Strapping improperly assembled	Visual	13006
202.	Nails improperly set or missing	Visual	13007
203.	Marking incomplete or incorrect	Visual	13008

4.3.3 *Testing.*

4.3.3.1 *Initial production* (see 4.2.1). The samples submitted as the initial production quantity shall be tested as specified below after having been examined for all other drawing requirements. Rejection and resubmission shall be in accordance with 4.2.3.

4.3.3.1.1 Presence of mounting insert pin (see dwg. 8861584 and 4.4.1)—Code No. 11010.

4.3.3.1.2 Leakage test of inert parts assembly (see 3.3 and 4.4.2)—Code No. 11011.

4.3.3.1.3 Weight of inert parts assembly (see dwg. 8861584 and 4.4.3)—Code No. 11012.

4.3.3.2 *Production testing.*

4.3.3.2.1 *Hardness of fragment (see dwg. 8800270)—Major defect—Code No. 14001.* The contractor shall establish an adequate procedure according to method 243 of Federal Test Method Standard No. 151 to assure fragment hardness within the limits specified on drawing 8800270. Test results shall be reported in such a manner that the Government inspector may readily assess the quality.

4.3.3.2.2 *Presence of mounting insert pin (see dwg. 8861584)—Major defect—Code No. 11010.* This determination shall be performed 100 percent as specified in 4.4.1 using the applicable inspection equipment of 4.3.4. Any assembly from which one or more pins are missing shall be classed defective and removed from the lot pending repair and resubmission to test.

4.3.3.2.3 *Leakage test of inert parts assembly (see 3.3)—Major defect—Code No. 11011.* This test shall be performed 100 percent. Any assembly which fails to comply with the requirement shall be classed defective and shall be removed from the lot. The test shall be performed as specified in 4.4.2.

4.3.3.2.4 *Weight of inert parts assembly (see dwg. 8861584)—Major defect—Code No. 11012.* This determination shall be performed 100 percent. Any assembly which fails to comply with the requirement of the drawing shall be classed defective and shall be removed from the lot. The test shall be performed as specified in 4.4.3.

4.3.3.2.5 *Molded components (see dwgs. 8861586, 8861587, and 8861588).* At the start of production from a new mold or after adjustment or repair to a mold, consecutively produced unts from each mold shall be dimensionally examined until 4 consecutive units meet all applicable drawing requirements. After adjustment or repair, those dimensions affected by the adjustment or repair shall be examined. During production, the molding procedures shall be monitored for uniformity of molding practices. Suspected deviations in mold product shall be examined to determine if corrective action or mold repair is required.

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

All dimensions for the thin body sections of the forward and aft bodies may be measured while under restraint to control the inherent out or round condition.

4.3.4 *Inspection equipment.* Index of Inspection Equipment Number IEL–8861584 identifies the inspection equipment required to perform the examinations and tests prescribed in this section. The contractor shall design inspection equipment in accordance with the instructions in paragraph 6.3.

4.3.4.1 *Government rights to documentation.* Inspection equipment drawings and lists provided and revised in accordance with the requirements of the IEL may be used by DOD activities for design, procurement, manufacture, testing, evaluation, production and receiving inspection, overhaul, shipping, storage, identification of stock, ordering and storage of replacement parts, inspection of items at overhaul, general maintenance of equipment, construction, survey and whenever inspection equipment drawings are needed.

4.3.4.2 *Supply and maintenance.* Supply and maintenance of the equipment listed on the IEL shall be in accordance with Specification MIL–I–45607.

4 3.4.3 *Government use of contractor's inspection and test equipment.* The contractor shall make available all inspection and test equipment necessary for determining conformance with contract requirements. Operation of the equipment and verification of its accuracy shall be supplied by the contractor for the performance of examination or test by the Government.

4.4 Test methods and procedures.

4.4.1 *Presence of mounting insert pin.* The cavity of each mounting insert shall be examined using the gage specified in 4.3.4. If the shoulder of the gage contacts one or more inserts of a unit, that unit shall be classed defective.

4.4.2 *Leakage test of inert parts assembly.* The inert parts assembly, prior to painting, shall be subjected to the internal air pressure specified in 3.3 while submerged under 1 inch of water. Any assembly exhibiting leakage, as evidenced by the escape of a stream of bubbles, of any frequency, shall be classed defective. Acceptable units shall be identified by a ½-inch letter "A" stamped on the closing plug seating surface.

4.4.3 *Weight of inert parts assembly.* The inert parts assembly shall be weighed using equipment accurate to with 0.01 pound. Any assembly, the weight of which is outside the range specified, shall be classed defective.

5. PREPARATION FOR DELIVERY

5.1 Packing and marking.

5.1.1 *Level C—Parts assembly (dwg. 8861584).* The assemblies shall be packed and marked in accordance with dwg. 8830879 or 8837892.

5.2 Data cards. Data cards shall be prepared for each lot. (see 6.1)

6. NOTES

6.1 Ordering data. Procurement documents shall specify the following:

(a) Title, number and date of this specification.

(b) Ammunition data cards shall be prepared for each lot in accordance with MIL–STD–1167.

6.2 Inspection code numbers. The five-digit code numbers assigned to the inspections herein are to facilitate future data collection and analysis by the Government.

6.3 Inspection equipment. The contractor shall design inspection equipment as

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

required by the referenced Inspection Equipment Lists (IEL) in accordance with the instructions of paragraphs 6.3.1 through 6.3.7.

6.3.1 *Inspection equipment lists.* Inspection equipment lists indicate the availability of inspection equipment designs by showing in the number column of the list of inspection equipment (00 Form 1242–3) the numbers of drawings of existing equipment designs or codes as indicated in paragraph 6.3.2. Design action required of the contractor with respect to the different types of drawings that may be listed is described in paragraphs 6.3.3 and 6.3.4. Action required by the contractor with respect to commercial inspection equipment is described in 6.3.5. The contractor will be required to prepare detailed drawings in accordance with 6.3.6 for all the equipment coded as Contractor Design in the number column. These contractor designs must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.2 *Inspection equipment list codes.* The inspection equipment as defined in 6.3.3, 6.3.4, 6.3.5 and 6.3.6 will be designated in the IEL by the following codes:

CDAF	— Contractor's design responsibility on Army format in accordance with MIL–D–45608.
CDCF	— Contractor's design responsibility on contractor format.
AD	— Army design.
ADMU	— Army design, mandatory for use.
CE	— Commercial equipment.
SCD	— Specification control drawing.

6.3.3 *Army designs.* Army designs are reflected on detailed drawings which completely depict all the information necessary for the fabrication of the item of inspection equipment. The contractor need provide no design when an Army design is listed for an item of inspection equipment. Army designs fall into two basic classifications, mandatory and non-mandatory. When an inspection equipment list references mandatory Army designs, the contractor shall comply with, and use these designs accordingly. The contractor may, however, in connection with non-mandatory designs and with the approval of the Government, design alternate inspection equipment or use comparable commercial equipment to facilitate his operations. Such contractor prepared designs or commercial equipment selections must be approved by the Government prior to fabrication or procuring of the equipment. Designs shall be submitted for approval as specified in 6.3.7.

6.3.4 *Specification control drawing.* Specification control drawings depict the minimum equipment requirements in outline, descriptive, diagramatic or pictorial form only and specify the required performance or other characteristics. Contractors must prepare detailed drawings (see 6.3.6) of their designs in support of specification control drawings. These contractor prepared designs must be approved by the Government prior to the fabrication or procuring of the equipment. Commercial equipment meeting the requirements of specification control drawings may be approved if described in sufficient detail to permit identification and evaluation by the Government. Designs shall be submitted for approval as specified in 6.3.7.

6.3.5 *Commercial equipment.* Commercial equipment is inspection equipment that has universal application for a specific function. It is comprised of items commonly used by industry and Government. Contractors are not required to furnish drawings of commercial inspection equipment, but a

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.

list of such equipment must be approved by the Government. Lists shall be submitted for approval to the inspection element of the agency administering the contract.

6.3.6 *Contractor designs.* Contractor designs are designs of inspection equipment for which the Government has assigned design responsibility to the contractor. Contractor designs shall be supported by detailed drawings which depict all information necessary to completely fabricate, calibrate and operate an item of inspection equipment. This requires that the necessary views, dimensions, materials, finish, notes, operating and calibration instructions be properly depicted in accordance with approved practices to the extent that further calculation or clarification will not be required. Contractor designs identified as CDCF may be developed on the format the contractor normally employs in his equipment design procedure provided such format reflects the detail and information specified above. Contractor designs identified as CDAF shall comply with the format and requirements of MIL–D–45608, and in addition, contain the detail and information specified above. Final approved contractor designs identified as CDCF shall be suitable for microfilming. They must be non-reproducible diazo or electrostatic prints of top quality full size with black lines on white background and shall provide a legible print produced via the 35MM microfilm process. Contractors shall submit one copy of the final design as a rolled set or flat set.

6.3.7 *Submission of contractor designs.* Designs shall be submitted for approval to the Commanding Officer, Picatinny Arsenal, ATTN. SMUPA–ND. Design review will normally be accomplished within one month after receipt by Picatinny Arsenal. Partial submission of inspection equipment designs is permissible and encouraged. However, the Arsenal completion date for design review will be based on the date of the final submission of designs.

6.4 Shipping containers. The procuring agency should notify the parts contractor of the possible availability of used wood shipping containers.

6.5 Quality assurance provisions of other documents. The quality assurance provisions of other documents of the contract which are required to be part of the contractor's written description include, but are not limited to, those which relate to plating or other protective coating, physical, chemical and other properties when specific quality assurance or inspection provisions are included in the applicable material or process specification.

6.6 Submission of initial production samples. Instructions, as to the location for the evaluation of the initial production sample shall be obtained from the contracting officer. Upon receipt of such request, the contracting officer shall advise Picatinny Arsenal and instructions will be issued accordingly. All inquiries should be forwarded to: Commanding Officer, Picatinny Arsenal, ATTN. SMUPA–NI.

Notice. When Government drawings, specifications, or other data are used for any purpose other than in connection with a definitely related Government procurement operation, the United States Government thereby incurs no responsibility nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use, or sell any patented invention that may in any way be related thereto.

Custodian:

Army—MU

Preparing activity:

Army—MU

Project No. 1336–A116

Source: https://assist.dla.mil -- Downloaded: 2026-10-22T03:05Z
Check the source to verify that this is the current version before use.