MIL-T-23449A(AS)
28 July 1969
Superseding
MIL-T-23449(WP)
1 February 1965

MILITARY SPECIFICATION

TRANSMITTING SET, RADIO AN/PRT-5(*)

This specification has been approved by the Naval Air Systems Command, Department of the Navy.

1. SCOPE

1.1 Scope - The equipment covered by this specification shall transmit a coded beacon signal on 8364 KHz and 243 MHz to provide homing signals for shore stations, searching ships, and aircraft. It shall provide for stowage in multi-place life rafts and operate with minimum effort upon inflation of the raft.

2. APPLICABLE DOCUMENTS

2.1 General - The following documents of the issue in effect on the date of invitation for bids form a part of this specification to the extent specified herein:

SPECIFICATIONS

MIL-E-5400	Electronic Equipment, Aircraft, General Specification for
MIL-T-5422	Testing, Environmental, Aircraft, Electronic Equipment
MIL-E-17555	Electronic and Electrical Equipment and Associated Repair Parts, Preparation for Delivery of
MIL-F-14072	Finish for Ground Signal Equipment
MIL-T-18303	Test Procedures; Preproduction and Inspection for Aircraft Electronic Equipment, Format for
MIL-N-18307	Nomenclature and Nameplates for Aeronautical Electronics and Associated Equipment

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

Federal Specifications

QQ-C-320	Chromium Plating, Electrodeposited
QQ-S-763	Steel Bars, Shapes, and Forgings, Corrosion Resisting

Naval Air Systems Command

AR-5	Microelectronic Devices Used in Avionic Equipment, Procedures for Selection and Approval of
AR-10	Maintainability of Avionics Equipment and Systems, General Requirements for

Standards

MIL-STD-781	Reliability Tests, Exponential Distribution

2.1.1 Availability of Documents

(1) When requesting specifications, standards, drawings, and publications, refer to both title and number. Copies of this specification and applicable specifications required by contractors in connection with specific procurement functions may be obtained upon application to the Commanding Officer, Naval Supply Depot, Code 105, 5801 Tabor Avenue, Philadelphia, Pennsylvania, 19120.

3. REQUIREMENTS

3.1 Preproduction - This specification makes provision for preproduction testing.

3.2 Parts and Materials - In the selection of parts and materials, fulfillment of major design objectives shall be the prime consideration. In so doing, the following shall govern:

(1) Microelectronic items shall conform to requirements specified herein.

(2) Other parts and materials requirements shall conform to Specification MIL-E-5400.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

(3) Non-repairable subassemblies, as outlined in Specification MIL-E-5400, shall be used when practicable. The general size of the subassembly and the amount of circuitry to be included therein shall be approved by the procuring activity. Non-repairable subassemblies must be reliable (See 6.5).

(4) When previously produced models of this equipment did not use non-repairable subassemblies, the design shall not be changed to emply non-repairable assemblies without the approval of the procuring activity.

3.2.1 Non-Standard Parts and Materials Approval - Approval for the use of non-standard parts and materials (including transistors and diodes) other than microelectronic devices, shall be obtained as outlined in Specification MIL-E-5400. Microelectronic devices shall be approved as outlined in AR-5.

3.2.2 Microelectronic Modular Assemblies - When used, microelectronic modular assemblies shall meet the requirements of Specification AR-5.

3.2.3 Modules - The electronic portions of the equipment shall be functionally modularized in accordance with Specification AR-10.

3.3 Design and Construction - The equipment shall conform with all the applicable requirements of Specification MIL-E-5400 for design, construction, and workmanship, except as otherwise specified herein.

3.3.1 Total Weight - The total weight of the equipment including battery and float collar shall be a minimum consistent with good design and shall not exceed 15 pounds.

3.3.2 Operating Life - The equipment shall have a total operating life of 10,000 hours with reasonable servicing and replacement of parts. Parts requiring scheduled replacement shall be specified by the contractor.

3.3.3 Reliability in Mean Time Between Failure (MTBF) - The equipment, including any Built-in-Test provisions, shall have 1,000 hours of mean (operating) time between failures when tested and accepted as outlined under the requirements 4.4.2.

3.3.4 Interchangeability - The equipment shall meet the interchangeability requirements of Specification MIL-E-5400.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

3.3.5 Provisions for Maintainability - Built-in test equipment, construction, and packaging, and provisions for test points shall be as specified in Specification AR-10.

3.3.6 Nomenclature and Nameplates - Nomenclature assignment and nameplate approval for equipment identification shall be in accordance with Specification MIL-N-18307.

3.3.7 Standard Conditions - The following conditions shall be used to establish normal performance characteristics under standard conditions and for making laboratory bench tests.

Temperature	Room ambient (25°C ± 5 C)
Altitude	Normal ground
Vibration	None
Humidity	Room ambient up to 90% relative humidity
Input voltage power	18.0 ± 0.5 VDC

3.3.8 Service Conditions - The equipment shall operate satisfactorily under any of the environmental conditions or reasonable combination of these conditions as specified in Specification MIL-E-5400 for Class I equipment, except as modified herein:

3.3.8.1 Vibration - The equipment shall operate satisfactorily when subjected to the vibration requirements of Curve IV of Specification MIL-E-5400.

3.3.8.2 Altitude - The equipment shall withstand without change the forces due to explosive decompression associated with a pressure differential of sea level (29.92 inches Hg) to 40,000 feet (5.54 inches Hg).

3.3.9 Warm-Up Time - The time required for the equipment to warm-up prior to operation shall be kept to a minimum and shall not exceed one second under standard conditions and five seconds at extreme service conditions.

3.3.10 Input Power Requirements - The transmitters shall operate from a battery capable of providing 72 hours continuous operation at 25°C with at least 250 milliwatts output from each transmitter at the end of this period. Low temperature operation capability shall be at least 48 hours at 0°C with at least 125 milliwatts output from each transmitter at the end of this period. The maximum intput power at 25°C shall be 250 milliamperes at 18.2 volts.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

3.3.11 Case Sealing - The assembly, including the antennas, shall be weatherproof, watertight, and dustproof and shall be capable of immersion in sea water for a period of 24 hours at a depth of two feet and a period of five minutes at a depth of 50 feet without leakage or electrical or mechanical damage to any components. Methods of sealing shall be such that after being opened for inspection, maintenance, and battery replacement, surfaces can easily be resealed to meet the requirements of this paragraph.

3.4 Performance - Unless otherwise specified, values set forth to establish the requirements for satisfactory performance apply to performance under both standard and extreme service conditions. When reduced performance under the extreme conditions is acceptable, tolerances or values setting forth acceptable variations from the performance under the standard conditions will be specified.

3.4.1 Operation - The AN/PRT-5 provides two output frequencies via two antennas. Both frequencies, the 8364 KHz and the 243 MHz, are transmitted simultaneously. The transmitters are modulated by a sweeping pulse modulated signal. A switch is provided to activate the unit.

3.4.2 Frequency Tolerance - The output frequency tolerance shall be $\pm 0.005\%$ for each transmitter under any combination of service conditions.

3.4.3 Frequency Characteristics - The output frequencies of the unit shall be 8364 KHz and 243 MHz, crystal controlled and fixed tuned.

3.4.4 Modulation Characteristics - The HF and UHF carriers shall be pulse modulated (PM) with a rectangular wave, periodically varying, audio frequency tone. The rectangular wave modulation shall provide a maximum/minimum duty cycle with carrier on-time for 10-15% of the cycle on HF and 45-55% of the cycle on UHF. The rectangular audio modulating wave shall periodically sweep in tone from $1000 \pm 20\%$ to $300 \pm 20\%$ Hz at a rate of 2 - 3 sweeps per second. The audio retrace from $300 \pm 20\%$ to $1000 \pm 20\%$ Hz shall require no more than 1 millisecond.

3.4.5 Transmitter Power Output - Each transmitter shall have a minimum average power of 0.5 watt (peak envelope power to be 1.0 watt nominal on the UHF transmitter and 5.0 watts nominal on the HF transmitter) at 18 ± 0.2 V at 25 C. For extreme service conditions the output shall be 250 milliwatts minimum at 18 ± 0.2 V.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

3.5 Detail Requirements - The Transmitting Set, Radio AN/PRT-5 shall meet the following requirements:

3.5.1 Function - The Transmitting Set shall provide for operation on land, hand-held in a life raft, and floating, supported by a flotation ring. It shall float in an operating position and shall not be damaged by complete immersion while transmitting. Fail safe keying shall be provided. Should the modulation or keyer signals to either transmitter module fail, the transmitters shall remain on with full peak power output. In addition to fail safe keying provisions, should either transmitter module fail, it shall not affect the performance of the other.

3.5.2 Form Factor - The transmitting set when packed for stowage shall be enclosed in a package 6 inches in diameter by 16 inches long.

3.5.3 Contents - The transmitting set shall consist of the following assemblies.

(1) Battery and case assembly
(2) Transmitter-Antenna assembly
(3) Float assembly
(4) Mooring line
(5) Carrying case

3.5.3.1 Battery and Case Assembly - A case shall be provided to house the battery. It shall be equipped so as to be opened for battery replacement and/or normal periodic maintenance. A complete set of operating instructions for placing the beacon in operation on land or sea shall be placed on each of two opposite sides of the case.

3.5.3.2 Transmitter-Antenna Assembly - The Transmitter-Antenna Assembly shall contain the antennas, the HF and UHF transmitters, and modulators, off-on control, and test cap. This assembly shall mount to the battery case with an O-Ring seal.

3.5.3.2.1 Antenna System - The antenna system shall consist of two vertical monopole antennas, one each to transmit on 8364 KHz and 243 MHz, respectively. The RF impedance of each antenna shall match the RF output impedance of the transmitter module to which it is connected. The HF antenna shall be telescoping to extend to 9 feet above the top of the transmitter case. It shall consist of .012 wall minimum type 304 stainless tubing welded and drawn per QQ-S-763 to provide a tensile strength of 120,000 to 140,000 p.s.i.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

Alternate sections shall be color coded to indicate to the downed airman that all sections are fully extended. The section immediately adjacent to the top of the transmitter case (and all odd sections) shall be Duramir BK chrome per QQ-C-320 passivated per MIL-F-14072,#300. The second section from the top of the transmitter case as well as the section internal to the transmitter and all even sections shall be sandblasted and passivated per MIL-F-14072,#300.

When positioned for stowage, the UHF antenna shall lay folded along the side of the battery case. The HF antenna shall telescope into the transmitter case. When positioned for transmission from water or land, the antenna shall be held vertical. The UHF antenna shall be flexible and be approximately a quarter wave length at 243 MHz. It shall be interchangeable with the antenna on the AN/PRC-90 radio.

3.5.3.3 Float Assembly - The float assembly shall be a doughnut shaped flotation ring, CO_2 inflatable, to support the transmitting set in an upright position when waterborne. It shall be equipped with an inflator to use Knapp-Monarch Company 2 oz. CO_2 bottle, or equivalent, Federal Stock Number 4220-837-3322. The inflator shall have provisions for discharging the bottle contents and inflating the flotation ring by pulling a lanyard. Provisions shall also be provided in the float assembly for oral inflation. The float assembly shall be capable of maintaining sufficient pressure to float in water for a period of at least 72 hours. Leaking during this period shall not affect the flotation or performance characteristics of the equipment.

3.5.3.4 Mooring Line - A nylon, or equivalent, mooring line at least 15 feet in length and 1/8 inch diameter shall be provided to moor the transmitting set to the life raft when floating. One end of the line shall be attached securely to the grommet in the outside edge of the flotation ring. A 3/4 inch snap hook shall be provided at the other end of the line.

3.5.3.5 Carrying Case - The carrying case shall provide a case for carrying and stowing the transmitting set. It shall be equipped with a handle for carrying the encased transmitting set. It shall have provisions for quick opening. It shall prevent chafing damage to enclosed equipment.

3.5.4 Controls - A SPST ON-OFF switch S1 shall be provided to control transmitter operation. The switch shall have provisions for being secured in the OFF position to prevent inadvertent transmitter operation.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

4. QUALITY ASSURANCE PROVISIONS

4.1 Responsibility for Inspection - Unless otherwise specified in the contract or purchase order, the supplier is responsible for the performance of all inspection requirements as specified herein. Except as otherwise specified, the supplier may utilize his own facilities or any commerical laboratory acceptable to the Government. The Government reserves the right to perform any of the inspections set forth in the specification where such inspections are deemed necessary to assure supplies and services conform to prescribed requirements.

4.1.1 Classification of Tests - Items covered by this specification shall be subjected to the following tests to determine compliance with all applicable documents.

(1) Preproduction (First Article) Tests
(2) Initial Production Tests
(3) Acceptance Tests
(4) Special Tests

4.2 Preproduction (First Article) Tests - Preproduction (First Article) tests shall be made on an equipment representative of the production equipments to be supplied under the contract. Preproduction tests shall be accomplished under the responsibility of the contractor and shall be conducted in accordance with the approved test procedure (See 4.5). The government inspector and the procuring activity shall be advised when tests are to be conducted so that a representative may be designated to witness or supervise the tests when so desired. Contractors not having adequate facilities to conduct all required tests shall obtain the services of a commerical testing laboratory acceptable to the Government.

4.2.1 Preproduction (First Article) Test Data - The contractor shall submit a Test Report including all data collected in conducting these tests to the procuring activity for review and approval within 5 days after completion of the tests.

4.2.2 Scope of Tests - Preproduction tests shall include all tests deemed necessary by the procuring activity to determine that the equipment meets all requirements of this specification and the contract. Preproduction tests shall include environmental tests in accordance with the procedures of Specification MIL-T-5422.

4.2.3 Preproduction (First Article) Approval - Approval of the preproduction sample shall be by the procuring activity upon satisfactory completion of all tests. No production equipments shall be delivered prior to the approval of the preproduction sample.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

Prefabrication of production equipment prior to the approval of the preproduction sample is at the contractor's own risk. The approved preproduction sample shall be retained by the contractor for his use in the fabrication and testing of equipment to be submitted for acceptance. The preproduction sample shall not be considered as one of the equipments under the contract.

4.2.4 Production Equipments - Equipments supplied under the contract shall in all respects, including design, construction, workmanship, performance and quality, be equivalent to the approved preproduction sample. Each equipment shall be capable of successfully passing the same tests as imposed on the preproduction sample. Evidence of non-compliance with the above shall constitute cause for rejection, and for equipment already accepted by the Government, it shall be the obligation of the contractor to make necessary corrections as approved by the procuring activity.

4.3 Initial Production Tests - One of the first 10 production equipments shall be selected and sent at the contractor's expense to a designated Government Laboratory for tests. This equipment shall be selected by the procuring activity after the equipment has successfully passed all individual tests. The preproduction sample shall not be selected for this test.

4.3.1 Scope of Tests - This equipment may be subjected to any and all tests the procuring activity deems necessary to assure that the production equipment is equivalent to the previously approved preproduction sample in design, construction, workmanship, performance and quality and that it meets all applicable requirements.

4.3.2 Accessory Material - In addition to the complete equipment submitted for Initial Production Tests, the contractor shall also submit such accessory material and data necessary to test the equipment.

4.3.3 Initial Production Sample Approval - Approval of the Initial Production sample shall be by the procuring activity upon satisfactory completion of all tests. Any design, material, or performance defect made evident during this test shall be corrected by the contractor to the satisfaction of the procuring activity. Failure of the Initial Production sample to pass any of the tests shall be cause for deliveries of equipment under the contract to cease until proper corrective action is approved and accomplished. Corrective action shall be accomplished on equipment previously accepted when requested by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

4.3.4 Reconditioning of Initial Production Test Sample - On completion of the initial production test, the equipment shall be reworked by the contractor by replacing all worn or damaged items. After reworking, the contractor shall resubmit the equipment for acceptance.

4.4 Acceptance Tests - The contractor shall furnish all samples and shall be responsible for accomplishing the acceptance tests. All inspection and testing shall be under the supervision of the government inspector. Contractors not having testing facilities satisfactory to the procuring activity shall engage the service of a commercial testing laboratory acceptable to the procuring activity. The contractor shall furnish test reports showing quantitative results for all acceptance tests. Such reports shall be signed by an authorized representative of the contractor or laboratory, as applicable. Acceptance or approval of material during the course of manufacture shall not be construed as a guarantee of the acceptance of the finished product. Acceptance tests shall consist of the following:

(1) Individual Tests
(2) Sampling Tests
(3) Reliability Assurance Tests
(4) Special Tests

4.4.1 Individual Tests - Each equipment submitted for acceptance shall be subjected to the individual tests. These tests shall be adequate to determine compliance with the requirements of material, workmanship, and operational adequacy. As a minimum, each equipment accepted shall have passed the following tests:

(1) Examination of Product
(2) Operational Test
(3) Manufacturing Run In Test (All Equipment Test)

4.4.1.1 Examination of Product - Each equipment shall be examined carefully to determine that the material and workmanship requirements have been met.

4.4.1.2 Operational Test - Each equipment shall be operated long enough to permit the equipment temperature to stabilize and to check sufficient characteristics and record adequate data to assure satisfactory equipment operation.

4.4.1.3 Manufacturing Run In Test (All Equipment Test) - Each equipment shall be vibration and temperature cycled under the conditions specified herein without failure. A failure shall be defined as anything which causes malfunctioning of the equipment.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

Only those adjustments will be permitted which can be made by using such controls and adjustments that are accessible to the operator during the normal use of the equipment.

During the 24-hour period of operation following the 10-minute vibration period, the equipment shall be mechanically cycled periodically through its various phases of operation. Should a failure occur, it should be repaired and the test started over, except that the 10-minute vibration period need not be repeated when it is certain the failure was not a result of the vibration. Should repetitive failures occur, corrective action shall be taken to eliminate this defect from future equipment. A record shall be kept of all failures. The periods specified above may be composed of three-hour periods to conform with standard working hours.

4.4.1.3.1 Vibration -

Temperature	Ambient room
Humidity	Ambient room
Vibration	Any selected frequency within the range of 20 to 30 cps (excluding resonant points) and a minimum amplitude of +3 g's.

The equipment shall be vibrated (without vibration isolators) for a period of 10 minutes prior to the beginning of the 24-hour period of temperature cycling (defined by 4.4.1.3.2). Where feasible, the equipment shall be operated during this vibration period for the purpose of detecting flaws and imperfect workmanship. Operation within the specified limits of satisfactory performance is not necessarily required during the vibration period. The direction of vibration should be vertical to the normal mounting plane for 5 minutes and lateral to the plane for 5 minutes. Where it is not feasible to vibrate the equipment in two directions, the vertical direction shall be used.

4.4.1.3.2 Temperature Cycling - Each unit shall be operated through a minimum of 8 temperature cycles as defined by the following:

High Temperature	131°F ± 5°F 30 min. operate + 15 min. Temperature stabilization period.
Low Temperature	85°F ± 5°F 2-1/2 hr. operate + 15 min. Temperature stabilization period.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

4.4.2 Reliability Assurance Tests - Reliability qualification tests shall be conducted to determine the equipment MTBF in accordance with MIL-STD-781. Equipments selected for reliability assurance tests shall first have passed the individual tests.

Prior to the acceptance of equipments under the contract or order, a minimum of three (3) equipments shall be tested as outlined in MIL-STD-781. The number of equipments to be used shall be in accordance with Table 5 of MIL-STD-781. Test level E shall be used. The Accept-Reject Criteria for Test Plan II shall be used. Each equipment shall be operated a minimum of 300 hours.

4.4.2.1 Length of Heat Portion of Cycle - After stabilization at the high temperature limit required by test level E (+55 C) the equipment shall be operated 3.0 hours during each cycle (as per 5.2.3.2 of MIL-STD-781B).

4.4.2.2 Performance Characteristics to be Measured - The following equipment characteristics are to be measured during the stabilized heat portion of the cycle:

(1) Modulation (per 3.4.4)
(2) Frequency Stability (per 3.4.2)
(3) Power Output (per 3.4.5)

4.4.2.3 Failure Criteria - In addition to the requirements of MIL-STD-781, whenever performance characteristics fall below the requirements of 3.4, at least one failure has occurred. If subsequent analysis reveals that several parts have deteriorated, each shall be counted a failure, unless one caused the other parts to fail.

4.4.2.4 Test Details - The test details such as the length of the test cycle, the length of the heat portion of the cycle, the performance characteristics to be measured, special failure criteria, preventive maintenance to be allowed during the test, etc., shall be part of the test procedure to be submitted and approved by the procuring activity prior to the beginning of the Qualification Test Phase of the Reliability Assurance Tests.

4.4.3 Special Tests - Special tests shall be conducted on a quantity of equipments for the purpose of checking the effect of any design or material change on the performance of the equipment and to assure adequate quality control. The equipment selected for special tests may be selected from equipments previously subjected to the reliability assurance tests.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

4.4.3.1 Special Test Schedule - Selection of equipments for special tests shall be made as follows:

(1) On an early equipment after an engineering or material change.
(2) Whenever failure reports or other information indicate additional tests are required. (This will be determined by the procuring activity.)

4.4.3.2 Scope of Tests - Special tests shall consist of such tests as approved by the procuring activity. Test procedures previously approved for the preproduction tests shall be used when applicable. When not applicable, the contractor shall prepare a test procedure and submit it to the procuring activity for approval prior to conducting the tests.

4.4.4 Equipment Failure - Should a failure occur during Manufacturing, Run In, Reliability, or Special Tests, the following action shall be taken:

(1) Determine the cause of failure.
(2) Determine if the failure is an isolated case or design defect.
(3) Submit to the procuring activity for approval, proposed corrective action intended to reduce the possibility of the same failure(s) occurring in future tests.
(4) Where practical, include a test in the individual test to check all equipment for this requirement until reasonable assurance is obtained that the defect has been satisfactorily corrected.

4.5 Test Procedures - The procedures used for conducting preproduction tests and acceptance tests shall be prepared by the contractor and submitted to the procuring activity for review and approval. The right is reserved by the procuring activity or the government inspector to modify the tests or require any additional tests deemed necessary to determine compliance with the requirements of this specification or the contract. Specification MIL-T-18303 shall be used as a guide for preparation of test procedures. When approved test procedures are available from previous contracts, such procedures will be provided and may be used when their use is approved by the procuring activity. However, the right is reserved by thr procuring activity to require modification of such procedures, including additional tests, when deemed necessary.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

4.6 Reconditioning of Tested Equipment - Equipment which has been subjected to extensive testing shall be reconditioned by the contractor by replacing all worn or damaged items. After reworking the contractor shall resubmit the equipment for acceptance.

4.7 Presubmission Testing - No item, part, or complete equipment shall be submitted by the contractor until it has been previously tested and inspected by the contractor and found to comply, to the best of his knowledge and belief, with all applicable requirements.

4.8 Rejection and Retest - Equipment which has been rejected may be reworked or have parts replaced to correct the defects and resubmitted for acceptance. Before resubmitting, full particulars concerning previous rejection and the action taken to correct the defects found in the original shall be furnished the government inspector.

5. PREPARATION FOR DELIVERY

5.1 General - All major units and parts of the equipment shall be preserved, packaged, packed and marked for the level of shipment specified in the contract or order in accordance with Specification MIL-E-17555.

6. NOTES

6.1 Intended Use - The equipment covered by this specification is intended primarily for emergency direction finding to airmen in life rafts.

6.2 Ordering Data - Purchasers should exercise any desired options offered herein, and procurement documents should specify the following:

(1) Title, number, and date of this specification
(2) Selection of applicable levels of packaging and packing in accordance with 5.1.

6.3 Precedence of Documents - When the requirements of the contract, this specification, or applicable subsidiary specifications are in conflict, the following precedence shall apply:

(1) Contract - The contract shall have precedence over any specification.
(2) This Specification - This specification shall have precedence over all applicable subsidiary specifications. Any deviation from this specification, or from subsidiary specifications where applicable, shall be specifically approved in writing by the procuring activity.

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

(3) Referenced Specifications - Any referenced specification shall have precedence over all applicable subsidiary specifications referenced therein. All referenced specifications shall apply to the extent specified.

6.4 Performance Objectives - Minimum size and weight, simplicity of operation, ease of maintenance, and an improvement in the performance and reliability of the specific functions beyond the requirements of this specification are objectives which shall be considered in the production of this equipment. Where it appears a substantial reduction in size and weight or improvement in simplicity of design, performance, ease of maintenance, or reliability will result from the use of materials, parts, and processes other than those specified in Specification MIL-E-5400, it is desired their use be investigated. When investigation shows advantages can be realized, a request for approval shall be submitted to the procuring activity for consideration. Each request shall be accompanied by complete supporting information.

6.5 Non-Repairable Subassemblies - As a general rule non-repairable subassemblies should be encapsulated or hermetically sealed. The number of connections internal to the subassembly should be held to a minimum. Detail parts tolerances and ratings should be so selected that the life of the subassembly is greater than that of a similar repairable one. With few exceptions (such as high voltage power supplies), the non-repairable subassembly should evidence a mean-time-to-failure greater than 5000 hours, and for many applications this figure must be nearer 50,000 hours.

6.6 Type Designations - The parentheses (*) when used in the equipment type designation, will be deleted or replaced by either a number or letter furnished by the procuring activity upon application by the contractor for assignment of nomenclature in accordance with 3.3.6. The complete type number shall be used on nameplates, shipping records, and instruction books, as applicable.

Project Number 5820 N449

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.

SPECIFICATION ANALYSIS SHEET

Form Approved
Budget Bureau No. 119-R004

INSTRUCTIONS

This sheet is to be filled out by personnel either Government or contractor, involved in the use of the specification in procurement of products for ultimate use by the Department of Defense. This sheet is provided for obtaining information on the use of this specification which will insure that suitable products can be procured with a minimum amount of delay and at the least cost. Comments and the return of this form will be appreciated. Fold on lines on reverse side, staple in corner, and send to preparing activity *(as indicated on reverse hereof)*.

SPECIFICATION
MIL-T-23449A(AS) TRANSMITTING SET, RADIO AN/PRT-5(*)

ORGANIZATION *(Of submitter)*	CITY AND STATE

CONTRACT NO.	QUANTITY OF ITEMS PROCURED	DOLLAR AMOUNT
		$

MATERIAL PROCURED UNDER A

☐ DIRECT GOVERNMENT CONTRACT ☐ SUBCONTRACT

1. HAS ANY PART OF THE SPECIFICATION CREATED PROBLEMS OR REQUIRED INTERPRETATION IN PROCUREMENT USE?

A. GIVE PARAGRAPH NUMBER AND WORDING.

B. RECOMMENDATIONS FOR CORRECTING THE DEFICIENCIES.

2. COMMENTS ON ANY SPECIFICATION REQUIREMENT CONSIDERED TOO RIGID

3. IS THE SPECIFICATION RESTRICTIVE?

☐ YES ☐ NO IF "YES", IN WHAT WAY?

4. REMARKS *(Attach any pertinent data which may be of use in improving this specification. If there are additional papers, attach to form and place both in an envelope addressed to preparing activity)*

SUBMITTED BY *(Printed or typed name and activity)*	DATE

DD, FORM 1 APR 63 1426

C-8270

Source: https://assist.dla.mil -- Downloaded: 2026-10-19T16:55Z
Check the source to verify that this is the current version before use.